Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

me of Work: Improvements and Maintenance Of Culverts at Santhosh Nagara in Ward No.13
ettyhalli Sub Division.

Est .Cost Rs.10.00 Lakhs

Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
KSRRB 300-3 Earthwork excavation by manual means for roads, drains & similar works in ordinary soil involving excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3, Page No 142/ Item No 19 1/ PWD SR 2018-19								
Santhosh Nagara		3	6 00	1 70	1 10	33 66		
		3	5.60	1 70	1.10	31 42		
		4	4 90	1 70	1.10	36 65		
	Cum					101.73	207.60	21118.73
KSRRB M2100-10 Providing and laying Plain cement concrete of mix 1:3 6 with OPC @ 220kgs. with crushed 40mm and down size graded granite metal coarse aggregates @0 89cum and fine aggregates @ 0 46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all matenals, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27 18)								
Santhosh Nagara		3	6.00	1.70	0.15	4.59		
		3	5.60	1.70	0.15	4.28		
		4	4.90	1.70	0.15	5.00		
	Cum					13.87	5421.90	75212.60
Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2,P No-271)								
Santhosh Nagara								
Bottom raft		3	6.00	1.50	0.15	4.05		
		3	5.60	1.50	0.15	3.78		
		4	4.90	1.50	0.15	4.41		
Wall		6	6.00	0.23	0.75	6.21		
		6	5.60	0.23	0.75	5.80		
		8	4.90	0.23	0.75	6.76		
For Deck Slab		3	6.00	1.50	0.30	8.10		
		3	5.60	1.50	0.30	7.56		
		4	4.90	1.50	0.30	8.82		
	Cum					55.49	7070.20	392311.26
KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2018-19								
Consider 90 kg /Cum For Culvert			55.49	90.00		4993.92		
	Ton's				Say	4.99	72326.98	361195.15
						Total construction cost		849837.74

Name of the Work: Improvements and ...

Scanned by CamScanner

Add GST Charge 12%	101980.53
Sub Total	951818.27
Tender premium 5%	47590.91
Miscellaneous and unforseen Charges	590.82
TOTAL	1000000.00

(Rupees Ten Lakhs Only)

CERTIFICATE

1 The Work spot has been inspected and the work found to be necessary
2 The Estimate is prepared as per the PWD SR 2018-19
3 The Provision made in estimate are adequate and essential
4 This area comes under BBMP limits.
5 This work is not included in any other estimate.

Asst Engineer
Ward No-13

Asst Executive Engineer
Shettyhalli Sub-Division
BBMP

Executive Engineer
Dasarahalli Zone
BBMP

Name of the Work Improvements and maintenance of Culvert

ನಂ. EE/DD/As/100/19-20 ದಿನಾಂಕ: 17/06/2019
Rs. 10.00 Lacs
Rupees Ten Lacs only
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE(DD)TS/68/18-19 ದಿನಾಂಕ: 30/01/19
ರೂ. Rs. Ten lacks only
(Rs. 10.00 Lacs)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner

Scanned by CamScanner